

Solar Eclipse and Control Room Update


Part 5

Energy Freedom Project

22 August 2017

Home Rooftop Solar Configuration

- Southwest roof with 28 panels
- Southeast roof with 9 panels
- maximum production capacity is 9.8 kW
- clouds are very disruptive but other phenomena are active




Energy Production

- Graphs of 4 production days with different performance are next
 - A near perfect solar energy production day
 - A really terrible solar energy production day
 - A day when Hydro One failed for a couple of hours
 - Solar Eclipse of 21 August 2017 (51% blockage)
- Graphs are Watt-hours vs. time of day
 - 15 minute time lapse vertical bars
- Lifetime Production from 3 April 2017
 - 6.8 megaWatt-hours

13 August 2017


Near perfect solar day

August 13, 2017 Produced
8:15 - 8:30 PM 0 Wh




Terrible Solar Day all due to clouds

July 24, 2017 Produced
10:00 - 10:15 AM **80 Wh**



Hydro One Power disruption Solar production shutdown


Cloud variations throughout the day



21 August 2017

51% Blockage Solar Eclipse

August 21, 2017 Produced
8:15 - 8:30 PM -- Wh



Solar Energy Performance

- Solar energy production is highly non-linear
- Predicting performance is low quality
- Expect the unexpected
- However, 6.8 megWatt-hour energy delivered to the Hydro One grid since March 2017

Progress Update

- The Energy Freedom Project is progressing
 - Solar subsystems are installed
 - Tesla home battery is expected very soon
 - Operations will take a substantial step forward
 - Ground Source Heat Pump design is preliminary
 - The Control Centre advances daily.
 - The following slides show advances since the part 4 update of 30 July 2017
 - Main task is Electric Vehicle and home energy load management


August 2017 Control Centre



Observations

- Box #1 (far left) is now a relay centre with an Arduino Mega in charge. Clear plastic permits viewing and protects wiring.
- The 7 foot rack on the right now has a pretty face. Still some trimming required.
- The cable runs on the top and bottom of the 5 boxes will be hidden soon.

Relay Complex



Observations

- There are 16 relays on the board on the right and another 8 available with add-on boards to the Arduino mega 256 (on the left).
- Many I/O pins are active. Only 7 relays are wired but many 5 VDC sensors are telling the software of the state of the main contactors.
- Clear plastic is standing off by 1 cm wooden blocks to permit ventilation.
- Finishing left of box will be done after the Tesla battery is installed on the plywood there.

Main Rack



Observations

- Mid-picture white board hides the many cables going to the 4 channel KVM (keyboard, video, mouse) switch. Only the manual push button and some status LEDs are visible.
- Above the KVM panel is the UPS (uninterruptible power supply) for emergency power to the electronics and one 4 Watt LED emergency light.
- Still some finishing required to close this right to the back wall.



Main Electronics Tower

- The grey box is the main contactor box shown previously in an update.
- Two whiteboard doors protect the upper chamber and the lower chamber of electrical equipment like power supplies and Raspberry Pi computers.
- Some finishing is still required to close out the lower right and add trim to equipment rack.

End Status Report

- The next status report will show the Tesla battery integrated into the Control Centre.